

SECTION 01 7419 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for the following:

- 1. Salvaging nonhazardous demolition and construction waste.
- 2. Recycling nonhazardous demolition and construction waste.
- 3. Disposing of nonhazardous demolition and construction waste.

- B. Related Requirements:

- 1. Section 011200 "Multiple Contract Summary" for coordination of responsibilities for waste management.
- 2. Section 024116 "Structure Demolition" for disposition of waste resulting from demolition of buildings, structures, and site improvements, and for disposition of hazardous waste.
- 3. Section 024119 "Selective Demolition" for disposition of waste resulting from partial demolition of buildings, structures, and site improvements, and for disposition of hazardous waste.
- 4. Section 042000 "Unit Masonry" for disposal requirements for masonry waste.
- 5. Section 044313.13 "Anchored Stone Masonry Veneer" for disposal requirements for excess stone and stone waste.
- 6. Section 044313.16 "Adhered Stone Masonry Veneer" for disposal requirements for excess stone and stone waste.
- 7. Section 311000 "Site Clearing" for disposition of waste resulting from site clearing and removal of above- and below-grade improvements.

1.3 DEFINITIONS

- A. Construction Waste: Building and site improvement materials and other solid waste resulting from construction, remodeling, renovation, or repair operations. Construction waste includes packaging.
- B. Demolition Waste: Building and site improvement materials resulting from demolition or selective demolition operations.
- C. Disposal: Removal off-site of demolition and construction waste and subsequent sale, recycling, reuse, or deposit in landfill or incinerator acceptable to authorities having jurisdiction.
- D. Recycle: Recovery of demolition or construction waste for subsequent processing in preparation for reuse.

- E. Salvage: Recovery of demolition or construction waste and subsequent sale or reuse in another facility.
- F. Salvage and Reuse: Recovery of demolition or construction waste and subsequent incorporation into the Work.

1.4 PERFORMANCE REQUIREMENTS

- A. General: Achieve end-of-Project rates for salvage/recycling of **[50] [75]** percent by weight of total non-hazardous solid waste generated by the Work. Practice efficient waste management in the use of materials in the course of the Work. Use all reasonable means to divert construction and demolition waste from landfills and incinerators. Facilitate recycling and salvage of materials, including the following:

1. Demolition Waste:

- a. Asphalt paving.
- b. Concrete.
- c. Concrete reinforcing steel.
- d. Brick.
- e. Concrete masonry units.
- f. Wood studs.
- g. Wood joists.
- h. Plywood and oriented strand board.
- i. Wood paneling.
- j. Wood trim.
- k. Structural and miscellaneous steel.
- l. Rough hardware.
- m. Roofing.
- n. Insulation.
- o. Doors and frames.
- p. Door hardware.
- q. Windows.
- r. Glazing.
- s. Metal studs.
- t. Gypsum board.
- u. Acoustical tile and panels.
- v. Carpet.
- w. Carpet pad.
- x. Demountable partitions.
- y. Equipment.
- z. Cabinets.
- aa. Plumbing fixtures.
- bb. Piping.
- cc. Supports and hangers.
- dd. Valves.
- ee. Sprinklers.
- ff. Mechanical equipment.
- gg. Refrigerants.
- hh. Electrical conduit.
- ii. Copper wiring.
- jj. Lighting fixtures.
- kk. Lamps.
- ll. Ballasts.

- mm. Electrical devices.
- nn. Switchgear and panelboards.
- oo. Transformers.
- pp. <Insert materials required>.

2. Construction Waste:

- a. Masonry and CMU.
- b. Lumber.
- c. Wood sheet materials.
- d. Wood trim.
- e. Metals.
- f. Roofing.
- g. Insulation.
- h. Carpet and pad.
- i. Gypsum board.
- j. Piping.
- k. Electrical conduit.
- l. Packaging: Regardless of salvage/recycle goal indicated in "General" Paragraph above, salvage or recycle 100 percent of the following uncontaminated packaging materials:
 - 1) Paper.
 - 2) Cardboard.
 - 3) Boxes.
 - 4) Plastic sheet and film.
 - 5) Polystyrene packaging.
 - 6) Wood crates.
 - 7) Plastic pails.
- m. <Insert materials required>.

1.5 ACTION SUBMITTALS

- A. Waste Management Plan: Submit plan within 7 days of date established for the Notice to Proceed.

1.6 INFORMATIONAL SUBMITTALS

- A. Waste Reduction Progress Reports: Concurrent with each Application for Payment, submit report. Include the following information:
 - 1. Material category.
 - 2. Generation point of waste.
 - 3. Total quantity of waste in tons (tonnes).
 - 4. Quantity of waste salvaged, both estimated and actual in tons (tonnes).
 - 5. Quantity of waste recycled, both estimated and actual in tons (tonnes).
 - 6. Total quantity of waste recovered (salvaged plus recycled) in tons (tonnes).
 - 7. Total quantity of waste recovered (salvaged plus recycled) as a percentage of total waste.

- B. Waste Reduction Calculations: Before request for Substantial Completion, submit calculated end-of-Project rates for salvage, recycling, and disposal as a percentage of total waste generated by the Work.
- C. Records of Donations: Indicate receipt and acceptance of salvageable waste donated to individuals and organizations. Indicate whether organization is tax exempt.
- D. Records of Sales: Indicate receipt and acceptance of salvageable waste sold to individuals and organizations. Indicate whether organization is tax exempt.
- E. Recycling and Processing Facility Records: Indicate receipt and acceptance of recyclable waste by recycling and processing facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.
- F. Landfill and Incinerator Disposal Records: Indicate receipt and acceptance of waste by landfills and incinerator facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.
- G. LEED Submittal: LEED letter template for Credit MR 2, signed by Contractor, tabulating total waste material, quantities diverted and means by which it is diverted, and statement that requirements for the credit have been met.
- H. Qualification Data: For waste management coordinator and refrigerant recovery technician.
- I. Statement of Refrigerant Recovery: Signed by refrigerant recovery technician responsible for recovering refrigerant, stating that all refrigerant that was present was recovered and that recovery was performed according to EPA regulations. Include name and address of technician and date refrigerant was recovered.

1.7 QUALITY ASSURANCE

- A. Waste Management Coordinator Qualifications: Experienced firm, with a record of successful waste management coordination of projects with similar requirements, that employs a LEED-Accredited Professional, certified by the USGBC, as waste management coordinator. [**Waste management coordinator may also serve as LEED coordinator.**]
- B. Refrigerant Recovery Technician Qualifications: Certified by EPA-approved certification program.
- C. Regulatory Requirements: Comply with hauling and disposal regulations of authorities having jurisdiction.
- D. Waste Management Conference: Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." Review methods and procedures related to waste management including, but not limited to, the following:
 - 1. Review and discuss waste management plan including responsibilities of waste management coordinator.
 - 2. Review requirements for documenting quantities of each type of waste and its disposition.
 - 3. Review and finalize procedures for materials separation and verify availability of containers and bins needed to avoid delays.

4. Review procedures for periodic waste collection and transportation to recycling and disposal facilities.
5. Review waste management requirements for each trade.

1.8 WASTE MANAGEMENT PLAN

- A. General: Develop a waste management plan according to ASTM E 1609 and requirements in this Section. Plan shall consist of waste identification, waste reduction work plan, and cost/revenue analysis. Distinguish between demolition and construction waste. Indicate quantities by weight or volume, but use same units of measure throughout waste management plan.
- B. Waste Identification: Indicate anticipated types and quantities of **[demolition]** **[site-clearing]** **[and]** **[construction]** waste generated by the Work. Include estimated quantities and assumptions for estimates.
- C. Waste Reduction Work Plan: List each type of waste and whether it will be salvaged, recycled, or disposed of in landfill or incinerator. Include points of waste generation, total quantity of each type of waste, quantity for each means of recovery, and handling and transportation procedures.
 1. Salvaged Materials for Reuse: For materials that will be salvaged and reused in this Project, describe methods for preparing salvaged materials before incorporation into the Work.
 2. Salvaged Materials for Sale: For materials that will be sold to individuals and organizations, include list of their names, addresses, and telephone numbers.
 3. Salvaged Materials for Donation: For materials that will be donated to individuals and organizations, include list of their names, addresses, and telephone numbers.
 4. Recycled Materials: Include list of local receivers and processors and type of recycled materials each will accept. Include names, addresses, and telephone numbers.
 5. Disposed Materials: Indicate how and where materials will be disposed of. Include name, address, and telephone number of each landfill and incinerator facility.
 6. Handling and Transportation Procedures: Include method that will be used for separating recyclable waste including sizes of containers, container labeling, and designated location where materials separation will be performed.
- D. Cost/Revenue Analysis: Indicate total cost of waste disposal as if there was no waste management plan and net additional cost or net savings resulting from implementing waste management plan. Include the following:
 1. Total quantity of waste.
 2. Estimated cost of disposal (cost per unit). Include hauling and tipping fees and cost of collection containers for each type of waste.
 3. Total cost of disposal (with no waste management).
 4. Revenue from salvaged materials.
 5. Revenue from recycled materials.
 6. Savings in hauling and tipping fees by donating materials.
 7. Savings in hauling and tipping fees that are avoided.
 8. Handling and transportation costs. Include cost of collection containers for each type of waste.
 9. Net additional cost or net savings from waste management plan.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 PLAN IMPLEMENTATION

- A. General: Implement approved waste management plan. Provide handling, containers, storage, signage, transportation, and other items as required to implement waste management plan during the entire duration of the Contract.
 - 1. Comply with operation, termination, and removal requirements in Section 015000 "Temporary Facilities and Controls."
- B. Waste Management Coordinator: Engage a waste management coordinator to be responsible for implementing, monitoring, and reporting status of waste management work plan. [**Coordinator shall be present at Project site full time for duration of Project.**]
- C. Training: Train workers, subcontractors, and suppliers on proper waste management procedures, as appropriate for the Work.
 - 1. Distribute waste management plan to everyone concerned within three days of submittal return.
 - 2. Distribute waste management plan to entities when they first begin work on-site. Review plan procedures and locations established for salvage, recycling, and disposal.
- D. Site Access and Temporary Controls: Conduct waste management operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
 - 1. Designate and label specific areas on Project site necessary for separating materials that are to be salvaged, recycled, reused, donated, and sold.
 - 2. Comply with Section 015000 "Temporary Facilities and Controls" for controlling dust and dirt, environmental protection, and noise control.

3.2 SALVAGING DEMOLITION WASTE

- A. Salvaged Items for Reuse in the Work: Salvage items for reuse and handle as follows:
 - 1. Clean salvaged items.
 - 2. Pack or crate items after cleaning. Identify contents of containers with label indicating elements, date of removal, quantity, and location where removed.
 - 3. Store items in a secure area until installation.
 - 4. Protect items from damage during transport and storage.
 - 5. Install salvaged items to comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make items functional for use indicated.
- B. Salvaged Items for Sale and Donation: Not permitted on Project site.
- C. Salvaged Items for Owner's Use: Salvage items for Owner's use and handle as follows:

1. Clean salvaged items.
2. Pack or crate items after cleaning. Identify contents of containers with label indicating elements, date of removal, quantity, and location where removed.
3. Store items in a secure area until delivery to Owner.
4. Transport items to Owner's storage area designated by Owner.
5. Protect items from damage during transport and storage.

D. Doors and Hardware: Brace open end of door frames. Except for removing door closers, leave door hardware attached to doors.

E. Equipment: Drain tanks, piping, and fixtures. Seal openings with caps or plugs. Protect equipment from exposure to weather.

F. Plumbing Fixtures: Separate by type and size.

G. Lighting Fixtures: Separate lamps by type and protect from breakage.

H. Electrical Devices: Separate switches, receptacles, switchgear, transformers, meters, panelboards, circuit breakers, and other devices by type.

3.3 RECYCLING DEMOLITION AND CONSTRUCTION WASTE, GENERAL

A. General: Recycle paper and beverage containers used by on-site workers.

B. Recycling Receivers and Processors: List below is provided for information only; available recycling receivers and processors include, but are not limited to, the following:

1. **<Insert names and telephone numbers of local recycling receivers and processors of recyclable materials>.**

C. Recycling Incentives: Revenues, savings, rebates, tax credits, and other incentives received for recycling waste materials shall accrue to Contractor.

D. Preparation of Waste: Prepare and maintain recyclable waste materials according to recycling or reuse facility requirements. Maintain materials free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to the recycling process.

E. Procedures: Separate recyclable waste from other waste materials, trash, and debris. Separate recyclable waste by type at Project site to the maximum extent practical according to approved construction waste management plan.

1. Provide appropriately marked containers or bins for controlling recyclable waste until removed from Project site. Include list of acceptable and unacceptable materials at each container and bin.
 - a. Inspect containers and bins for contamination and remove contaminated materials if found.
2. Stockpile processed materials on-site without intermixing with other materials. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.
3. Stockpile materials away from construction area. Do not store within drip line of remaining trees.
4. Store components off the ground and protect from the weather.

5. Remove recyclable waste from Owner's property and transport to recycling receiver or processor.

3.4 RECYCLING DEMOLITION WASTE

- A. Asphalt Paving: Break up and transport paving to asphalt-recycling facility.
- B. Concrete: Remove reinforcement and other metals from concrete and sort with other metals.
- C. Masonry: Remove metal reinforcement, anchors, and ties from masonry and sort with other metals.
 1. Clean and stack undamaged, whole masonry units on wood pallets.
- D. Wood Materials: Sort and stack members according to size, type, and length. Separate lumber, engineered wood products, panel products, and treated wood materials.
- E. Metals: Separate metals by type.
 1. Structural Steel: Stack members according to size, type of member, and length.
 2. Remove and dispose of bolts, nuts, washers, and other rough hardware.
- F. Asphalt Shingle Roofing: Separate organic and glass-fiber asphalt shingles and felts. Remove and dispose of nails, staples, and accessories.
- G. Gypsum Board: Stack large clean pieces on wood pallets or in container and store in a dry location. Remove edge trim and sort with other metals. Remove and dispose of fasteners.
- H. Acoustical Ceiling Panels and Tile: Stack large clean pieces on wood pallets and store in a dry location.
- I. Metal Suspension System: Separate metal members including trim, and other metals from acoustical panels and tile and sort with other metals.
- J. Carpet and Pad: Roll large pieces tightly after removing debris, trash, adhesive, and tack strips.
 1. Store clean, dry carpet and pad in a closed container or trailer provided by Carpet Reclamation Agency or carpet recycler.
- K. Carpet Tile: Remove debris, trash, and adhesive.
 1. Stack tile on pallet and store clean, dry carpet in a closed container or trailer provided by Carpet Reclamation Agency or carpet recycler.
- L. Piping: Reduce piping to straight lengths and store by type and size. Separate supports, hangers, valves, sprinklers, and other components by type and size.
- M. Conduit: Reduce conduit to straight lengths and store by type and size.

3.5 RECYCLING CONSTRUCTION WASTE

- A. Packaging:

1. Cardboard and Boxes: Break down packaging into flat sheets. Bundle and store in a dry location.
2. Polystyrene Packaging: Separate and bag materials.
3. Pallets: As much as possible, require deliveries using pallets to remove pallets from Project site. For pallets that remain on-site, break down pallets into component wood pieces and comply with requirements for recycling wood.
4. Crates: Break down crates into component wood pieces and comply with requirements for recycling wood.

B. Wood Materials:

1. Clean Cut-Offs of Lumber: Grind or chip into small pieces.
2. Clean Sawdust: Bag sawdust that does not contain painted or treated wood.

C. Gypsum Board: Stack large clean pieces on wood pallets or in container and store in a dry location.

3.6 DISPOSAL OF WASTE

A. General: Except for items or materials to be salvaged, recycled, or otherwise reused, remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.

1. Except as otherwise specified, do not allow waste materials that are to be disposed of accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

B. Burning: Do not burn waste materials.

C. Disposal: Remove waste materials from Owner's property and legally dispose of them.

3.7 ATTACHMENTS

- A. Form CWM-1 for construction waste identification.
- B. Form CWM-2 for demolition waste identification.
- C. Form CWM-3 for construction waste reduction work plan.
- D. Form CWM-4 for demolition waste reduction work plan.
- E. Form CWM-5 cost/revenue analysis of construction waste reduction work plan.
- F. Form CWM-6 cost/revenue analysis of demolition waste reduction work plan.
- G. Form CWM-7 for construction waste
- H. Form CWM-8 for demolition waste.

END OF SECTION 01 7419

NORTHWESTERN UNIVERSITY
PROJECT NAME _____
JOB # _____

FOR: _____
ISSUED: 03/29/2017

THIS PAGE IS INTENTIONALLY BLANK

NORTHWESTERN UNIVERSITY
 PROJECT NAME _____
 JOB # _____

FOR: _____
 ISSUED: 03/29/2017

| FORM CWM-1: CONSTRUCTION WASTE IDENTIFICATION | | | | | | | |
|---|------------------|--|--------------------|---|---------------------|---------------------------|-------------------------|
| MATERIAL CATEGORY | GENERATION POINT | EST. QUANTITY OF MATERIALS RECEIVED* (A) | EST. WASTE - % (B) | TOTAL EST. QUANTITY OF WASTE* (C = A X B) | EST. VOLUME CY (CM) | EST. WEIGHT TONS (TONNES) | REMARKS AND ASSUMPTIONS |
| Packaging: Cardboard | | | | | | | |
| Packaging: Boxes | | | | | | | |
| Packaging: Plastic Sheet or Film | | | | | | | |
| Packaging: Polystyrene | | | | | | | |
| Packaging: Pallets or Skids | | | | | | | |
| Packaging: Crates | | | | | | | |
| Packaging: Paint Cans | | | | | | | |
| Packaging: Plastic Pails | | | | | | | |
| Site-Clearing Waste | | | | | | | |
| Masonry or CMU | | | | | | | |
| Lumber: Cut-Offs | | | | | | | |
| Lumber: Warped Pieces | | | | | | | |
| Plywood or OSB (scraps) | | | | | | | |
| Wood Forms | | | | | | | |
| Wood Waste Chutes | | | | | | | |
| Wood Trim (cut-offs) | | | | | | | |
| Metals | | | | | | | |
| Insulation | | | | | | | |
| Roofing | | | | | | | |
| Joint Sealant Tubes | | | | | | | |
| Gypsum Board (scraps) | | | | | | | |
| Carpet and Pad (scraps) | | | | | | | |
| Piping | | | | | | | |
| Electrical Conduit | | | | | | | |
| Other: | | | | | | | |

* Insert units of measure.

NORTHWESTERN UNIVERSITY
 PROJECT NAME _____
 JOB # _____

FOR: _____
 ISSUED: 03/29/2017

| FORM CWM-2: DEMOLITION WASTE IDENTIFICATION | | | | |
|---|---------------|------------------------|------------------------------|-------------------------|
| MATERIAL DESCRIPTION | EST. QUANTITY | EST. VOLUME CY (CM) | EST. WEIGHT TONS (TONNES) | REMARKS AND ASSUMPTIONS |
| Asphaltic Concrete Paving | | | | |
| Concrete | | | | |
| Brick | | | | |
| CMU | | | | |
| Lumber | | | | |
| Plywood and OSB | | | | |
| Wood Paneling | | | | |
| Wood Trim | | | | |
| Miscellaneous Metals | | | | |
| Structural Steel | | | | |
| Rough Hardware | | | | |
| Insulation | | | | |
| Roofing | | | | |
| Doors and Frames | | | | |
| Door Hardware | | | | |
| Windows | | | | |
| Glazing | | | | |
| Acoustical Tile | | | | |
| Carpet | | | | |
| Carpet Pad | | | | |
| Demountable Partitions | | | | |
| Equipment | | | | |
| Cabinets | | | | |
| Plumbing Fixtures | | | | |
| Piping | | | | |
| Piping Supports and Hangers | | | | |
| Valves | | | | |
| Sprinklers | | | | |
| Mechanical Equipment | | | | |
| Electrical Conduit | | | | |
| Copper Wiring | | | | |
| Light Fixtures | | | | |
| Lamps | | | | |
| Lighting Ballasts | | | | |
| Electrical Devices | | | | |
| Switchgear and Panelboards | | | | |
| Transformers | | | | |
| Other: | | | | |

NORTHWESTERN UNIVERSITY
 PROJECT NAME _____
 JOB # _____

FOR: _____
 ISSUED: 03/29/2017

FORM CWM-3: CONSTRUCTION WASTE REDUCTION WORK PLAN

| MATERIAL CATEGORY | GENERATION POINT | TOTAL EST. QUANTITY OF WASTE TONS (TONNES) | DISPOSAL METHOD AND QUANTITY | | | HANDLING AND TRANSPORTION PROCEDURES |
|----------------------------------|------------------|--|------------------------------------|------------------------------------|--|--------------------------------------|
| | | | EST. AMOUNT SALVAGED TONS (TONNES) | EST. AMOUNT RECYCLED TONS (TONNES) | EST. AMOUNT DISPOSED TO LANDFILL TONS (TONNES) | |
| Packaging: Cardboard | | | | | | |
| Packaging: Boxes | | | | | | |
| Packaging: Plastic Sheet or Film | | | | | | |
| Packaging: Polystyrene | | | | | | |
| Packaging: Pallets or Skids | | | | | | |
| Packaging: Crates | | | | | | |
| Packaging: Paint Cans | | | | | | |
| Packaging: Plastic Pails | | | | | | |
| Site-Clearing Waste | | | | | | |
| Masonry or CMU | | | | | | |
| Lumber: Cut-Offs | | | | | | |
| Lumber: Warped Pieces | | | | | | |
| Plywood or OSB (scraps) | | | | | | |
| Wood Forms | | | | | | |
| Wood Waste Chutes | | | | | | |
| Wood Trim (cut-offs) | | | | | | |
| Metals | | | | | | |
| Insulation | | | | | | |
| Roofing | | | | | | |
| Joint Sealant Tubes | | | | | | |
| Gypsum Board (scraps) | | | | | | |
| Carpet and Pad (scraps) | | | | | | |
| Piping | | | | | | |
| Electrical Conduit | | | | | | |
| Other: | | | | | | |

NORTHWESTERN UNIVERSITY
 PROJECT NAME _____
 JOB # _____

FOR: _____
 ISSUED: 03/29/2017

FORM CWM-4: DEMOLITION WASTE REDUCTION WORK PLAN

| MATERIAL CATEGORY | GENERATION POINT | TOTAL EST. QUANTITY OF WASTE TONS (TONNES) | DISPOSAL METHOD AND QUANTITY | | | HANDLING AND TRANSPORTION PROCEDURES |
|----------------------------|------------------|--|------------------------------------|------------------------------------|--|--------------------------------------|
| | | | EST. AMOUNT SALVAGED TONS (TONNES) | EST. AMOUNT RECYCLED TONS (TONNES) | EST. AMOUNT DISPOSED TO LANDFILL TONS (TONNES) | |
| Asphaltic Concrete Paving | | | | | | |
| Concrete | | | | | | |
| Brick | | | | | | |
| CMU | | | | | | |
| Lumber | | | | | | |
| Plywood and OSB | | | | | | |
| Wood Paneling | | | | | | |
| Wood Trim | | | | | | |
| Miscellaneous Metals | | | | | | |
| Structural Steel | | | | | | |
| Rough Hardware | | | | | | |
| Insulation | | | | | | |
| Roofing | | | | | | |
| Doors and Frames | | | | | | |
| Door Hardware | | | | | | |
| Windows | | | | | | |
| Glazing | | | | | | |
| Acoustical Tile | | | | | | |
| Carpet | | | | | | |
| Carpet Pad | | | | | | |
| Demountable Partitions | | | | | | |
| Equipment | | | | | | |
| Cabinets | | | | | | |
| Plumbing Fixtures | | | | | | |
| Piping | | | | | | |
| Supports and Hangers | | | | | | |
| Valves | | | | | | |
| Sprinklers | | | | | | |
| Mechanical Equipment | | | | | | |
| Electrical Conduit | | | | | | |
| Copper Wiring | | | | | | |
| Light Fixtures | | | | | | |
| Lamps | | | | | | |
| Lighting Ballasts | | | | | | |
| Electrical Devices | | | | | | |
| Switchgear and Panelboards | | | | | | |
| Transformers | | | | | | |
| Other: | | | | | | |

NORTHWESTERN UNIVERSITY
 PROJECT NAME _____
 JOB # _____

FOR: _____
 ISSUED: 03/29/2017

| FORM CWM-5: COST/REVENUE ANALYSIS OF CONSTRUCTION WASTE REDUCTION WORK PLAN | | | | | | | | |
|---|--|---------------------------|---|-------------------------------------|-------------------------------------|-----------------------------------|---|---|
| MATERIALS | TOTAL QUANTITY OF MATERIALS (VOL. OR WEIGHT) (A) | EST. COST OF DISPOSAL (B) | TOTAL EST. COST OF DISPOSAL (C = A x B) | REVENUE FROM SALVAGED MATERIALS (D) | REVENUE FROM RECYCLED MATERIALS (E) | LANDFILL TIPPING FEES AVOIDED (F) | HANDLING AND TRANSPORTATION COSTS AVOIDED (G) | NET COST SAVINGS OF WORK PLAN (H = D+E+F+G) |
| Packaging: Cardboard | | | | | | | | |
| Packaging: Boxes | | | | | | | | |
| Packaging: Plastic Sheet or Film | | | | | | | | |
| Packaging: Polystyrene | | | | | | | | |
| Packaging: Pallets or Skids | | | | | | | | |
| Packaging: Crates | | | | | | | | |
| Packaging: Paint Cans | | | | | | | | |
| Packaging: Plastic Pails | | | | | | | | |
| Site-Clearing Waste | | | | | | | | |
| Masonry or CMU | | | | | | | | |
| Lumber: Cut-Offs | | | | | | | | |
| Lumber: Warped Pieces | | | | | | | | |
| Plywood or OSB (scraps) | | | | | | | | |
| Wood Forms | | | | | | | | |
| Wood Waste Chutes | | | | | | | | |
| Wood Trim (cut-offs) | | | | | | | | |
| Metals | | | | | | | | |
| Insulation | | | | | | | | |
| Roofing | | | | | | | | |
| Joint Sealant Tubes | | | | | | | | |
| Gypsum Board (scraps) | | | | | | | | |
| Carpet and Pad (scraps) | | | | | | | | |
| Piping | | | | | | | | |
| Electrical Conduit | | | | | | | | |
| Other: | | | | | | | | |

NORTHWESTERN UNIVERSITY
 PROJECT NAME _____
 JOB # _____

FOR: _____
 ISSUED: 03/29/2017

| FORM CWM-6: COST/REVENUE ANALYSIS OF DEMOLITION WASTE REDUCTION WORK PLAN | | | | | | | | |
|---|---|------------------------------|--|--|--|--------------------------------------|--|--|
| MATERIALS | TOTAL QUANTITY OF MATERIALS (VOL. OR WEIGHT) (A) | EST. COST OF DISPOSAL (B) | TOTAL EST. COST OF DISPOSAL (C = A x B) | REVENUE FROM SALVAGED MATERIALS (D) | REVENUE FROM RECYCLED MATERIALS (E) | LANDFILL TIPPING FEES AVOIDED (F) | HANDLING AND TRANSPORTATION COSTS AVOIDED (G) | NET COST SAVINGS OF WORK PLAN (H = D+E+F+G) |
| Asphaltic Concrete Paving | | | | | | | | |
| Concrete | | | | | | | | |
| Brick | | | | | | | | |
| CMU | | | | | | | | |
| Lumber | | | | | | | | |
| Plywood and OSB | | | | | | | | |
| Wood Paneling | | | | | | | | |
| Wood Trim | | | | | | | | |
| Miscellaneous Metals | | | | | | | | |
| Structural Steel | | | | | | | | |
| Rough Hardware | | | | | | | | |
| Insulation | | | | | | | | |
| Roofing | | | | | | | | |
| Doors and Frames | | | | | | | | |
| Door Hardware | | | | | | | | |
| Windows | | | | | | | | |
| Glazing | | | | | | | | |
| Acoustical Tile | | | | | | | | |
| Carpet | | | | | | | | |
| Carpet Pad | | | | | | | | |
| Demountable Partitions | | | | | | | | |
| Equipment | | | | | | | | |
| Cabinets | | | | | | | | |
| Plumbing Fixtures | | | | | | | | |
| Piping | | | | | | | | |
| Supports and Hangers | | | | | | | | |
| Valves | | | | | | | | |
| Sprinklers | | | | | | | | |
| Mech. Equipment | | | | | | | | |
| Electrical Conduit | | | | | | | | |
| Copper Wiring | | | | | | | | |
| Light Fixtures | | | | | | | | |
| Lamps | | | | | | | | |
| Lighting Ballasts | | | | | | | | |
| Electrical Devices | | | | | | | | |
| Switchgear and Panelboards | | | | | | | | |
| Transformers | | | | | | | | |
| Other: | | | | | | | | |

NORTHWESTERN UNIVERSITY
 PROJECT NAME _____
 JOB # _____

FOR: _____
 ISSUED: 03/29/2017

| FORM CWM-7: CONSTRUCTION WASTE REDUCTION PROGRESS REPORT | | | | | | | | |
|--|------------------|---|----------------------------|--------------------------|----------------------------|--------------------------|---|---|
| MATERIAL CATEGORY | GENERATION POINT | TOTAL QUANTITY OF WASTE TONS (TONNES) (A) | QUANTITY OF WASTE SALVAGED | | QUANTITY OF WASTE RECYCLED | | TOTAL QUANTITY OF WASTE RECOVERED TONS (TONNES) (D = B + C) | TOTAL QUANTITY OF WASTE RECOVERED % (D / A x 100) |
| | | | ESTIMATED TONS (TONNES) | ACTUAL TONS (TONNES) (B) | ESTIMATED TONS (TONNES) | ACTUAL TONS (TONNES) (C) | | |
| Packaging: Cardboard | | | | | | | | |
| Packaging: Boxes | | | | | | | | |
| Packaging: Plastic Sheet or Film | | | | | | | | |
| Packaging: Polystyrene | | | | | | | | |
| Packaging: Pallets or Skids | | | | | | | | |
| Packaging: Crates | | | | | | | | |
| Packaging: Paint Cans | | | | | | | | |
| Packaging: Plastic Pails | | | | | | | | |
| Site-Clearing Waste | | | | | | | | |
| Masonry or CMU | | | | | | | | |
| Lumber: Cut-Offs | | | | | | | | |
| Lumber: Warped Pieces | | | | | | | | |
| Plywood or OSB (scraps) | | | | | | | | |
| Wood Forms | | | | | | | | |
| Wood Waste Chutes | | | | | | | | |
| Wood Trim (cut-offs) | | | | | | | | |
| Metals | | | | | | | | |
| Insulation | | | | | | | | |
| Roofing | | | | | | | | |
| Joint Sealant Tubes | | | | | | | | |
| Gypsum Board (scraps) | | | | | | | | |
| Carpet and Pad (scraps) | | | | | | | | |
| Piping | | | | | | | | |
| Electrical Conduit | | | | | | | | |
| Other: | | | | | | | | |

NORTHWESTERN UNIVERSITY
 PROJECT NAME _____
 JOB # _____

FOR: _____
 ISSUED: 03/29/2017

| FORM CWM-8: DEMOLITION WASTE REDUCTION PROGRESS REPORT | | | | | | | | |
|--|------------------|---|----------------------------|--------------------------|----------------------------|--------------------------|---|---|
| MATERIAL CATEGORY | GENERATION POINT | TOTAL QUANTITY OF WASTE TONS (TONNES) (A) | QUANTITY OF WASTE SALVAGED | | QUANTITY OF WASTE RECYCLED | | TOTAL QUANTITY OF WASTE RECOVERED TONS (TONNES) (D = B + C) | TOTAL QUANTITY OF WASTE RECOVERED % (D / A x 100) |
| | | | ESTIMATED TONS (TONNES) | ACTUAL TONS (TONNES) (B) | ESTIMATED TONS (TONNES) | ACTUAL TONS (TONNES) (C) | | |
| Asphaltic Concrete Paving | | | | | | | | |
| Concrete | | | | | | | | |
| Brick | | | | | | | | |
| CMU | | | | | | | | |
| Lumber | | | | | | | | |
| Plywood and OSB | | | | | | | | |
| Wood Paneling | | | | | | | | |
| Wood Trim | | | | | | | | |
| Miscellaneous Metals | | | | | | | | |
| Structural Steel | | | | | | | | |
| Rough Hardware | | | | | | | | |
| Insulation | | | | | | | | |
| Roofing | | | | | | | | |
| Doors and Frames | | | | | | | | |
| Door Hardware | | | | | | | | |
| Windows | | | | | | | | |
| Glazing | | | | | | | | |
| Acoustical Tile | | | | | | | | |
| Carpet | | | | | | | | |
| Carpet Pad | | | | | | | | |
| Demountable Partitions | | | | | | | | |
| Equipment | | | | | | | | |
| Cabinets | | | | | | | | |
| Plumbing Fixtures | | | | | | | | |
| Piping | | | | | | | | |
| Supports and Hangers | | | | | | | | |
| Valves | | | | | | | | |
| Sprinklers | | | | | | | | |
| Mechanical Equipment | | | | | | | | |
| Electrical Conduit | | | | | | | | |
| Copper Wiring | | | | | | | | |
| Light Fixtures | | | | | | | | |
| Lamps | | | | | | | | |
| Lighting Ballasts | | | | | | | | |
| Electrical Devices | | | | | | | | |
| Switchgear and Panelboards | | | | | | | | |
| Transformers | | | | | | | | |
| Other: | | | | | | | | |